



ARIZONA DEPARTMENT OF AGRICULTURE
Weights and Measures Services Division

1688 West Adams Street Phoenix, Arizona 85007
Metrology Laboratory: 4425 W. Olive Ave, Suite 134, Glendale, AZ 85302
602-771-4920 FAX 623-939-8586 800-277-6675
<https://dwm.az.gov>

Stage II Decommissioning Reference Guide

This guide is meant to be a summary of the requirements and does not remove any obligation of a regulated party to follow any rules or statute requirements in Arizona Revised Statutes Title 3, Chapter 19 or Arizona Administrative Code Title 20, Chapter 2.

1. The rules for decommissioning may be found at:
<https://dwm.az.gov/sites/default/files/documents/files/StageII2015.pdf>
2. Submit a notice of intent form online 10 days prior to decommissioning (R20-2-913(F)) at the following link:
https://ctutools.azda.gov/dwm/pv/Vapor058_LocationSearch.asp
3. If there are any changes to the date of decommissioning, file a new notice of intent form online at the same link 24 hours prior to construction.
4. Decommission in accordance with the Petroleum Equipment Institute (PEI) Recommended Practice 300, and additionally purge any liquid from the vapor piping at required under R20-2-713(H). The PEI RP 300 can be purchased online at <http://www.pei.org/rp300> or we have a copy at the office that is available for viewing.
5. Leave a copy of the checklist on site following decommissioning. This may be in electronic form (from the online submittal in #6 below) or paper form. A copy of the paper form is on our website under "Forms>Vapor Recovery."
6. Submit the checklist required under R20-2-713(I) online at the same link in #1 above within 10 days of completion.
7. Schedule and conduct vapor recovery testing within 60 days following completion of decommissioning (R20-2-713(J)). Testing shall be scheduled and conducted by a licensed vapor Registered Service Representative and shall be scheduled on the Division's online vapor recovery scheduler as a "vapor decommission test." Testing shall consist of a 2" pressure decay, pressure vacuum vent valve, and tie tank test as outlined in R20-2-1005.

Email any questions or issues to dwm@azda.gov

